


MV/LV transformer testing instructions

Insulation resistance measurement • Winding resistance measurement





v1.01 | 23.05.2022

Overview




Internal connections



Designations

TRANSFORMATOR			
Typ	T0d630/10	Liczba faz	3
Moc [kVA]	630	Grupa połączeń	Dyn5
Napięcie GN [V]	10500	REGUL.	+2,5% -3x2,5%
Napięcie DN [V]	400		
Prąd GN [A]	34,64	Prąd DN [A]	909,33
Nap. zwar. [%]	6,12	Łącz. tot. [Hz]	50
Straty jał. [W]	730	Straty Ład. [W]	7553
Poziom izol. GN	LI75AC28	Poziom izol. DN	AC2,5
Chłodzenie	ONAN	Praca	
Masa całkow. [kg]	2000	Masa cz. wyjm. [kg]	1345
Masa oleju [kg]	330	Według Normy PN-83/E-06040	
Rok	1999		
Nr	37753		
	Olej: TECHNOL 2002		



Key

D delta connection, high voltage side
Y star connection, high voltage side
D zigzag connection, high voltage side
N neutral conductor, high voltage side

d delta connection, low voltage side
y star connection, low voltage side
z zigzag connection, low voltage side
n neutral conductor, low voltage side
n*30° angular displacement of the low voltage side vector in relation to the high voltage side vector
n hour displacement – multiplication of the angle of 30°

U_{GN} rated voltage of HV side
 U_{DN} rated voltage of LV side
 I_{GN} rated current of HV side
 I_{DN} rated current of LV side

1 Prepare for measurement



Earth the transformer.



Carefully clean the insulators.




Determine the transformer winding temperature Θ :


- 10–15 hours after filling with oil or de-energisation
- with a thermometer (measurement at the 2/3 of the tank height) or
- using resistance method (measurement of average winding temperature) or
- with a thermal imaging camera.

If it is possible to change voltage at the HV taps, they must be set at all three HV windings. Otherwise balance current causing demagnetisation of the transformer core will flow through the windings.

2 Carry out visual inspection



3 Earth the transformer before measurement




2 min


4

4 Connect the meter to the transformer


HV winding relative to the LV side and the tank




LV winding relative to the HV side and the tank



HV winding relative to the LV side (with shield)



HV+LV relative to the tank earth



5 Enter measurement setpoints



$$U_{ISO} \geq 2.5 \text{ kV}$$


Voltage according to the operating and maintenance manual or test voltage from the test carried out by the manufacturer.




measurement time

Depending on the transformer group (I, II, III).

6 Start measurement and read the results



Measurement monitoring via mobile app SONEL MIC MOBILE



7 Convert the result to reference temperature

Reference temperature is 30°C. Resistance is converted according to the following dependence:

$$R_{ISO(30^{\circ}C)} = k_1 \cdot R_{ISO(\theta)}$$

where:

- $R_{ISO(30^{\circ}C)}$ resistance converted to reference temperature,
- k_1 correction factor depending on winding temperature θ (step ①),
- $R_{ISO(\theta)}$ measured resistance.

The correction factor k_1 can be determined using the following table.

θ [°C]	0	5	10	15	18	21	24	27	30	33	36	39	42	45	50	55
k_1 [-]	0.25*	0.32*	0.39*	0.50	0.57	0.66	0.76	0.87	1.0	1.14	1.32	1.52	1.74	2.0	2.52*	3.18*

* indicative value

8

Evaluate the results

GROUP I

Insulation resistance between:

- windings and earth $R_{ISO(30^{\circ}C)} > (1/C) \cdot 1000 \text{ M}\Omega$
- windings $R_{ISO(30^{\circ}C)} \geq (5/C) \cdot 1000 \text{ M}\Omega$

where:

- C system capacitance [nF]

GROUP II

Insulation resistance between:

- windings and earth $R_{ISO(30^{\circ}C)} > 70 \text{ M}\Omega$
- windings $R_{ISO(30^{\circ}C)} \geq 150 \text{ M}\Omega$

GROUP III

Insulation resistance between:

- windings and earth $R_{ISO(30^{\circ}C)} \geq 35 \text{ M}\Omega$

GROUP IV

Resistance for transformers:

- $U_n > 10 \text{ kV}$ $R_{ISO(30^{\circ}C)} > 20 \text{ M}\Omega$
- $U_n \leq 10 \text{ kV}$ $R_{ISO(30^{\circ}C)} > 15 \text{ M}\Omega$

...except for cast-resin transformers where:

- HV/LV system, HV/earth $> 1000 \text{ M}\Omega$
- LV/earth system $> 20 \text{ M}\Omega$

$$\text{DAR}_{\text{standard 1}} = \frac{R_{ISO_60s}}{R_{ISO_30s}}$$

$$\text{DAR}_{\text{standard 2}} = \frac{R_{ISO_60s}}{R_{ISO_15s}}$$

$$\text{DAR}_{\text{standard 3}} = \frac{R_{ISO_300s}}{R_{ISO_60s}}$$

$\geq$ **DAR**
from
acceptance
tests

The results should be compared to the historical test reports, including the manufacturer's tests.

9

Set the date for subsequent testing



- In 2 years?
- In 5 years?
- According to the manufacturer's recommendations?
- Specific case? (For example after a month-long downtime.)

1 Prepare for measurement



Earth and decouple the transformer.



Carefully clean the transformer terminal at the connection, so that contact resistance has no influence on the measurement result.




Determine the transformer winding temperature Θ :

- 10–15 hours after filling with oil or de-energisation,
- with a thermometer (measurement at the 2/3 of the tank height) or
- using resistance method (measurement of average winding temperature) or
- with a thermal imaging camera.




Identify the winding material.


2 Carry out visual inspection




3 Earth the transformer.



4 Identify the transformer connection system.



5 Connect the meter to the windings



6 Enter measurement setpoints




- Measurement mode
- One-way measurement
- Algorithm
- Maximum measurement current (max. 15% of I_n of the winding)




- ☒ Temperature compensation
- ☒ Ambient temperature
- ☒ Item/winding temperature
- α Winding material or its temperature coefficient α
- ☒ Reference temperature

7 Start measurement and read the results



8 Obtain winding resistance




$$R_a = \frac{2 \cdot R_{UV} \cdot R_{WV}}{R_{UV} + R_{VW} - R_{UW}} - \frac{R_{UV} + R_{WV} - R_{UW}}{2}$$

$$R_b = \frac{2 \cdot R_{UV} \cdot R_{WV}}{R_{UW} + R_{VW} - R_{UV}} - \frac{R_{UV} + R_{WV} - R_{UW}}{2}$$

$$R_c = \frac{2 \cdot R_{UV} \cdot R_{UW}}{R_{UW} + R_{UV} - R_{WV}} - \frac{R_{UW} + R_{UV} - R_{WV}}{2}$$

Star without N




$$R_a = \frac{R_{UV} + R_{WU} - R_{VW}}{2}$$

$$R_b = \frac{R_{UV} + R_{VW} - R_{WU}}{2}$$

$$R_c = \frac{R_{WU} + R_{VW} - R_{UV}}{2}$$

Star with N



$$R_a = R_{UN}$$

$$R_b = R_{VN}$$

$$R_c = R_{WN}$$

Measurements of all transformer windings should be performed on all tap changer steps.

9 Evaluate the results

For each tap the results should meet the following criteria:

$$R_a = (100\% \pm 5\%) R_{a_factory}$$

$$R_b = (100\% \pm 5\%) R_{b_factory}$$

$$R_c = (100\% \pm 5\%) R_{c_factory}$$

$$R_a = (100\% \pm 3\%) \frac{R_{a_factory} + R_{b_factory} + R_{c_factory}}{3}$$

$$R_b = (100\% \pm 3\%) \frac{R_{a_factory} + R_{b_factory} + R_{c_factory}}{3}$$

$$R_c = (100\% \pm 3\%) \frac{R_{a_factory} + R_{b_factory} + R_{c_factory}}{3}$$

10 Set the date for subsequent testing



- In 5 years?
- According to the manufacturer's recommendations?

		SYSTEM ZAPEWNIENIA JAKOŚCI	PROTOKÓŁ PRÓB TRANSFORMATORA						
ISO 9001		ZAKŁAD TRANSFORMATORÓW DZIAŁ KONTROLI JAKOŚCI							
Typ	T0d 630/10		Nr fabr.	37 753					
Moc	630	kVA	Rok prod.	1999					
Napięcie GN	10 500	V	Grupa pol.	Dyn5					
Stopnie reg.	+2,5-3x2,5	%	Prąd GN	34,64	A				
Napięcie DN	400	V	Prąd DN	909,33	A				
Masa całk.	2 000	kg	Masa cz.wyjm	1 345	kg				
Norma	PN - 83/E - 06040		Poziom izol.	LI75AC28/AC2,5					
Zlecenie	DT040-902553/1		Praca	C					
Częstotliwość	50	Hz	Temp. otocz.	40	°C				
Chłodzenie	ON-AN		Masa oleju	330	kg				
Napięcie zw.	6,12	%							
1. Rezystancja uzwojeń [Ω] w temperaturze 20 °C									
Uzwojenie	Zaczep	1U1V	1U1W	1V1W	Średnio na fazę				
	1	1,59	1,59	1,59	2,38				
	2	1,55	1,55	1,55	2,32				
GN	3	1,51	1,51	1,51	2,27				
	4	1,47	1,47	1,47	2,21				
	5	1,43	1,44	1,43	2,15				
DN	-	2N2U	2N2V	2N2W	-				
	-	0,0011	0,0011	0,0011	0,0011				
2. Rezystancja izol. [MΩ] w tem 20 °C Megaomierz 2,5 kV									
		R ₆₀	R ₁₅	R ₆₀ /R ₁₅					
G-D,Z		15 290	10 670	1,43					
D-G,Z		16 540	8 340	1,98					
3. Badanie oleju: Olej spełnia wymagania PN-83/E - 06040									
4. Sprawdzenie przekładni i grupy połączeń									
Zaczep	1	2	3	4	5				
U _N	26,91	26,25	25,59	24,94	24,28				
Δu _{max} [%]	0,2								
Stwierdzono grupę połączeń:	Dyn5								
5. Próba wytrzymałości elektrycznej 5.1 Próba napięciem doprowadzonym 50 Hz ; 60s GN DN Wynik: Pozytywny 5.2 Próba napięciem indukowanym. Zasilono uzwojenie DN napięciem 2 x U _N ; 100Hz; 60s. Pozytywny									
6. Próba stanu jałowego Zasilano uzwojenie DN									
f	Napięcie				Prąd				Moc
	2U2V	2U2W	2V2W	Średnio	2U	2V	2W	Średnio	Σ
Hz	V	V	V	V	A	A	A	A	W
50	398	401	401	400	4,19	3,30	4,44	3,98	730
Straty jałowe gw. 0,800 kW Straty jałowe zmierzone 0,730 kW Odchyłka 0,00 % Prąd jałowy gw. 0,40 % In Prąd jałowy zmierzony 0,44 % In 9,33 %									
7. Próba zwarcia pomiarowego: Zasilano uz GN Zwarto uzw. DN u _{ol} 20 °C									
f	Napięcie				Prąd				Moc
	1U1V	1U1W	1V1W	Średnio	1U	1V	1W	Średnio	Σ
Hz	V	V	V	V	A	A	A	A	W
50	531	535	534	533,3	28,80	28,80	28,60	28,73	4490
Straty obciążeniowe gw. 6,75 kW Straty obciążeniowe zm. 7,55 kW Odchyłka 11,89 % Napięcie zwarcia gw. 6,00 % Napięcie zwarcia zm. 6,12 % 2,06 %									
8. Sprawdzenie działania przełącznika zaczepów: Wykonano wg PN-81/E-04070.02 Wynik: Pozytywny 9. Badanie szczelności kadzi: Wykonano wg PN-81/E-04070.04 Wynik: Pozytywny									
UWAGI: 					Transformator spełnia wymagania PN - 83/E - 06040				
Żychlin, dnia 20 października 1999									
Mierzyl:					Zatwierdził:				